

ITEM 647.30----25 - BRIDGE SIGN REMOVAL, STORAGE AND REMOUNTING

1. DESCRIPTION:

- 1.01 This work shall consist of the removal, storage and remounting of the bridge mounted signs shown on the Plans, specified in the Contract documents, or ordered by the Engineer.

2. MATERIALS:

- 2.01 All bolts, nuts or washers unable to be reused shall be supplied by the Contractor and meet the requirements of NYS Standard Specifications Section 715-16 – Stainless Steel Connecting Products.

3. CONSTRUCTION DETAILS:

- 3.01 The Contractor shall remove the sign, supporting members, and connections as shown on the Plans or ordered by the Engineer. He will then pack and protect these materials, deliver and store them at a site approved by the Engineer. Upon completion of the bridge, rehabilitation or at such time as the Engineer orders, the Contractor shall remove the sign and all its appurtenances from the storage area, deliver it to the site and remount on the bridge as shown on the Plans or ordered by the Engineer.
- 3.02 All materials not used will become the property of the Thruway Authority.
- 3.03 It will be the Contractor's responsibility to deliver the sign to and from storage. He will be totally responsible for maintaining the sign during dismantling, delivery and erection. Any damage to the sign or its appurtenances during these operations will be repaired or replaced by the Contractor at no cost to the Thruway Authority.
- 3.04 The Contractor will be responsible for damages to the sign or its appurtenances while in storage.
- 3.05 If the sign is to be replaced, the Contractor shall turn over the existing sign to the Authority and the Authority shall provide a new fabricated sign.

4. METHOD OF MEASUREMENT:

- 4.01 The quantity to be paid for under the work will be the number of signs and associated appurtenances removed, stored and reinstalled as shown on the Plans or directed by the Engineer.

5. BASIS OF PAYMENT:

- 5.01 The unit price bid for each sign shall be compensation in full for removal, delivery to and from storage and reinstallation of the sign. This will include all labor and materials and transportation necessary to properly complete the work as shown on the Plans and called for in the Specification.