

**ITEM 699.04----25 - MOBILIZATION**

**1. DESCRIPTION:**

1.01 Under this item the work the Contractor shall be generally compensated for expenses which are incurred before significant contract work occurs. The three (3) milestones identified by the NYSTA for successful Contractor completion of mobilization to begin this public works contract are:

a. **Start of Work:**

Provide the necessary bonds, insurance, and prefinancing.

Set up the necessary general plant, including shops, storage areas, offices for itself and the Owner's Engineer and such sanitary and other facilities as are required by local or state law or regulation, and staff the project with equipment.

b. **Schedule of Operations:**

Submit, and if necessary, revise and resubmit, a complete "Critical Path format Schedule of Operations" as described in §108-01, of the TA Addendum.

c. **Minority and Women's Business Enterprise Participation Program:**

Provide a M/WBE participation program meeting the M/WBE goals of the Contract as described in **§109-06 CONTRACT PAYMENTS** and in accordance with **§102-12 D/M/WBE UTILIZATION**.

**2. MATERIALS:**

2.01 Unless otherwise specified, materials required for mobilization, but not installed as part of the completed contract, shall be as determined by the Contractor, except they shall conform to any pertinent local, State or Federal laws, regulations or codes.

**3. CONSTRUCTION DETAILS:**

3.01 The work required to provide the above facilities, services, and equipment for mobilization shall be done in a safe and workmanlike manner and shall conform with any pertinent local, State or Federal Law, regulation or code. Good housekeeping consistent with safety and other requirements of this contract shall be maintained.

**4. METHOD OF MEASUREMENT:**

4.01 Payment for mobilization will be made on a lump sum basis in the next estimate after the acceptable completion of all three (3) mobilization milestones, as documented by the Engineer:

- a. Milestone 1 is submission of required bonds, insurance, and refinancing.
- b. Milestone 2 is acceptance of a CPM Schedule of Operations for the project in accordance with §108-01 of the TA Addendum.

**ITEM 699.04----25 - MOBILIZATION**

**4. METHOD OF MEASUREMENT:** (cont'd)

4.01 (cont'd)

- c. Milestone 3 is acceptance of the Contractor's program to comply with the M/WBE goals of the Contract in accordance with **§102-12 D/M/WBE UTILIZATION**.

**5. BASIS OF PAYMENT:**

- 5.01 The amount bid for mobilization shall not exceed four percent (4%) of the total contract bid price, excluding the bid price for mobilization.

The amount bid shall constitute only general compensation for the furnishing and maintenance of the services and facilities delineated in Section 1. Description, to the extent and at the time the Contractor deems them necessary for his operations, consistent with the requirements of this work and the contract.

The amount bid shall be payable to the Contractor with the first progress estimate made for other contract work following acceptable completion of all three (3) milestones defining completion of the work of this Item. The first progress estimate shall be made after the value of contract work, excluding the value of this item, meets the requirements set forth in **§109-06 – Contract Payments**.

Payment will be made under:

<b><u>ITEM NO.</u></b>	<b><u>DESCRIPTION</u></b>	<b><u>PAY UNIT</u></b>
699.04      25	Mobilization	Lump Sum