

ITEM 654.49--25 - REMOVAL OF IMPACT ATTENUATION DEVICES

1. DESCRIPTION:

- 1.01 This work shall include the removal and disposal or storage of existing impact attenuation devices as designated on the plans or as specified by the Engineer.

2. MATERIALS:

- 2.01 The device to be removed can be any type commonly in use. The Contractor shall inspect the site to determine the exact type.
- 2.02 The Contractor shall furnish acceptable dunnage for devices to be stored above ground.

3. CONSTRUCTION DETAILS:

- 3.0 The existing devices shall be removed and stockpiled above ground in a neat and workmanlike manner, to the satisfaction of the Engineer, by the Contractor at the sites designated on the plans or by the Engineer. All hardware shall be bagged and labeled.
- 3.02 The Contractor shall transport the devices in a workmanlike manner so as not to damage any of the parts.
- 3.03 Where the devices contain expendable items such as sand, water, glycol solutions, etc. these items shall be removed and disposed of by the Contractor.
- 3.04 The location from which the devices are removed shall be cleaned and restored to a usable condition. All exposed metal fastening devices shall be burned off flush with the surface.
- 3.05 All parts shall be disconnected or unscrewed not cut or burned apart. They shall be disconnected in a manner which will allow the reuse of the device.
- 3.06 The Contractor shall submit to the Engineer a list of parts, by size and type, which have been acceptably stored.

4. METHOD OF MEASUREMENT:

- 4.01 The quantity to be paid for will be the number of installations completely removed and disposed or stored.

5. BASIS OF PAYMENT:

- 5.01 The unit price bid for removing an existing installation shall be compensation in full for the furnishing of all labor equipment and materials necessary to complete the work to the satisfaction of the Engineer.