

ITEM 645.5130--25 - MOUNT OVERHEAD SIGN PANELS (AUTHORITY SUPPLIED)
ITEM 645.52----25 - INSTALL GROUND MOUNT SIGN PANELS (AUTHORITY SUPPLIED)

1. DESCRIPTION:

- 1.01 Under this work the Contractor shall mount overhead or ground mounted panels supplied by the Authority on existing sign structures or sign structures to be constructed as part of this Contract, all in accordance with the Plans, Standard Sheets and Specifications or as approved by the Engineer.

2. MATERIALS:

- 2.01 All materials used for mounting overhead or ground mounted sign panels shall be furnished by the Contractor and shall meet the requirements of Section 645-2, Materials, of the Standard Specifications.

3. CONSTRUCTION DETAILS:

- Sign panels shall be mounted in accordance with the requirements of Section 645-3, Construction Details, of the Standard Specifications.
- 3.01 **Maintenance of Traffic.** Sign panels are to be mounted above active traffic lanes. Adequate maintenance of traffic measures shall be employed, all in accordance with Section 619 of the Standard Specifications, the New York State Manual of Uniform Traffic Control Devices or as directed by the Engineer.
- 3.02 The Contractor shall give the Engineer 4 week's minimum notice of his need for the sign panels furnished by the Authority.

4. METHOD OF MEASUREMENT:

- 4.01 The work shall be measured as the number of square feet of sign panel to be mounted as shown on the Plans or as directed by the Engineer. The area of sign panel shall be measured as the product of the plan height and width. The area shall be computed to the nearest ¼ square foot with no reduction for rounded corners.

5. BASIS OF PAYMENT:

- 5.01 The unit price bid for each square foot of sign panel shall be compensation in full for mounting and adjusting sign panels as required, all in accordance with the Plans, Standard Sheets or as directed by the Engineer. The work shall include all material, equipment and labor necessary to complete the job to the satisfaction of the Engineer, including transportation of the sign panels from the Authority delivery point to the work site.