

**ITEM 615.26—25 - BICYCLE RACK**

**1. DESCRIPTION:**

- 1.01 The work shall consist of furnishing and installing bicycle rack(s) where indicated in the Contract Documents or as ordered by the Engineer.

**2. MATERIALS:**

- 2.01 A. The bicycle rack(s) shall be model as manufactured by:

Maglin Furniture Systems, Ltd.  
27 Bysham Park Drive  
Woodstock, Ontario, Canada N4A 1P1  
[REDACTED]

Model: MBR100  
Color: Black Standard

Or approved equal by the N.Y.S. Thruway Authority Landscape Architect.

- B. The bicycle rack for State Historic Sites shall be model as manufactured by:

Pilot Rock Park Equipment  
R. J. Thomas Manufacturing Co., Inc.  
P.O. Box 946  
Cherokee, Iowa 51012-0946  
[REDACTED]

Model: BR-12/DS  
Color/Finish: Hot-Dip Galvanized

Or approved equal by the N.Y.S. Office of Parks, Recreation and Historic Preservation.

- 2.02 The footing concrete for the bicycle rack shall conform to the requirements for Class A Concrete specified in Section 501, Portland Cement, General.
- 2.03 Anchor studs, nuts and washers - ASTM A307.
- 2.04 All mounting anchor studs, nuts and washers shall be galvanized in accordance with the requirements of Subsection 719-01.
- 2.05 Drilling and grouting anchor studs shall conform to the requirements of Subsection 701-07.
- 2.06 Finishes: Black powder coating.

**3. CONSTRUCTION DETAILS:**

- 3.01 Bicycle rack(s) shall be installed with anchoring and footings as specified by the manufacturer or as indicated on the Contract Documents.

**ITEM 615.26----25 - BICYCLE RACK**

**4. METHOD OF MEASUREMENT:**

- 4.01 Bicycle rack(s) shall be measured by each bicycle rack unit as specified on the Contract Documents acceptably placed and approved by the Engineer.

**5. BASIS OF PAYMENT:**

- 5.01 The unit price bid per bicycle rack shall include all labor, material and equipment necessary to complete the work.