

ITEM 606.6201--25 - REMOVING AND STORING HEAVY POST BLOCKED-OUT CORRUGATED BEAM GUIDE RAIL

1. DESCRIPTION:

- 1.01 This work shall consist of the removal and storage of existing heavy post blocked-out corrugated beam guide rail, posts and component parts in accordance with this specification and as shown on the plans or as directed by the Engineer.

2. MATERIALS:

- 2.01 None Specified.

3. CONSTRUCTION DETAILS:

- 3.01 The Contractor shall remove the existing heavy post blocked-out corrugated beam guide rail, transport, and neatly store its component parts in separate piles at locations designated by the New York State Thruway Authority forces or its designee. The work shall be done in a workmanlike manner so as to salvage all usable parts. Unusable material shall be disposed of by the Contractor. Proper precautions shall be taken to protect traffic at all times.

4. METHOD OF MEASUREMENT:

- 4.01 Measurement will be made as the number of feet, center to center of end posts, of heavy post blocked-out corrugated beam guide rail removed and stored as herein specified or ordered by the Engineer. If the heavy post blocked-out corrugated beam guide rail is anchored to a structure, payment will be made for the measured length up to the structure.

5. BASIS OF PAYMENT:

- 5.01 The unit price bid per foot shall include the cost of furnishing all labor, equipment and material necessary to complete the work, including all costs necessary to transport and store the heavy post blocked-out corrugated beam guide rail, posts and component parts.