

ITEM 645.35----25 – INSTALL SIGN PANELS ON CHAIN LINK FENCE

1. DESCRIPTION:

- 1.01 This work shall consist of installing Authority supplied sign panels onto existing chain link fence as described in the contract plans and as directed by the Engineer.

2. MATERIALS:

- 2.01 All materials used for installing sign panels shall be furnished by the Contractor and shall meet the requirements of the Section 645-2, Materials, of the Standard Specifications.

3. CONSTRUCTION DETAILS:

- 3.01 Sign panels shall be mounted in accordance with the Plans, Standard Sheets and the requirements of Section 645-3, Construction Details, of the Standard Specifications.
- 3.02 The Contractor shall notify the Engineer eight weeks prior to his need for the sign panels to be furnished by the Authority.

4. METHOD OF MEASUREMENT:

- 4.01 This work will be measured as the number of sign panels, of the size shown on the Plans, satisfactorily installed on chain link fence in accordance with the contract documents and as directed by the Engineer.

5. BASIS OF PAYMENT:

- 5.01 The unit price bid for installing each sign panel on chain link fence shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work, including transportation of the sign panels from the Authority delivery point to the work site.