


P:\DWG\DWG\2\DESIGN\B\B\Current Thruway Standard Sheets\General\TREE REMOVAL.dwg
DRAWN BY: B. KOSLOSKE
CHECKED BY: B. HOWARD
DESIGNED BY: TA
BUREAU DIRECTOR: TA

ITEM	DESCRIPTION
203.03	EMBANKMENT IN PLACE
614.03XX	TREE REMOVAL



TREE REMOVAL

ENVIRONMENTAL NOTES:

- TREE REMOVAL AND PROTECTION OF WETLANDS:** TREE REMOVAL SHALL BE COMPLETED BY EITHER CLEARING OR SELECTIVE CUTTING METHODS, AND ONLY AS INDICATED ON THE PLANS. CLEARING AND GRUBBING OF TREES IN FEDERAL WETLANDS SHOULD BE AVOIDED AND MINIMIZED WHENEVER POSSIBLE. RIGHT-OF-WAY, SAFETY, AND DRAINAGE ISSUES SHOULD NOT BE COMPROMISED BY TREE CLEARING AVOIDANCE AND MINIMIZATION EFFORTS. THE CONTRACTOR SHALL TAKE CARE NOT TO ENTER WETLAND AREAS ADJACENT TO DESIGNATED TREE CLEARING AND SELECTIVE REMOVAL LOCATIONS. ACTIVITIES THAT ARE NOT TO ENCROACH ON ADJACENT WETLANDS INCLUDE MOVEMENT OF VEHICLES, CONSTRUCTION STAGING, DISPOSAL OF WOOD CHIPPINGS, PLACEMENT OF EROSION CONTROL FEATURES, AND SPREADING OF SPOILED SOIL, AMONG OTHERS.
- PAYMENT FOR EACH TREE REMOVAL SHALL INCLUDE THE WORK REQUIRED FOR REMOVAL OF THE RESPECTIVE STUMP. EXISTING STUMPS SHOWN ON THE PLANS (FROM TREES THAT WERE CUT DOWN BY MAINTENANCE FORCES) SHALL BE REMOVED UNDER ITEM 614.0394 - TREE REMOVAL EXISTING STUMP, STUMPS GRUBBED.

TREE REMOVAL LOCATIONS					
APPROX. MILEPOST	PLAN SHEET NUMBER	TREE DIAMETER (D.B.H.)	TREE COMMON NAME	QUANTITY	ITEM NUMBER
XXX.XX E.B. RT.	XX-X	24"	POPLAR	3	614.0342
XXX.XX E.B. RT.	XX-X	10"	ELM	2	614.0322
XXX.XX E.B. RT.	XX-X	5 FT.	COTTONWOOD	1	614.0382
XXX.XX E.B. RT.	XX-X	14"	ELM	1	614.0332
XXX.XX E.B. RT.	XX-X	18"-22"	ASH	7	614.0342
XXX.XX E.B. RT.	XX-X	4" - 6"	ELM	15	614.0314
XXX.XX E.B. RT.	XX-X	12"	POPLAR	1	614.0322
XXX.XX E.B. RT.	XX-X	42"	POPLAR	1	614.0362
XXX.XX E.B. RT.	XX-X	32"	POPLAR	1	614.0353
XXX.XX W.B. RT.	XX-X	4.5 FT.	COTTONWOOD	1	614.0373
XXX.XX W.B. RT.	XX-X	1' - 6"	EXISTING STUMPS	14	614.0394
XXX.XX W.B. RT.	XX-X	14"-16"	BLACK LOCUST	2	614.0332
XXX.XX W.B. RT.	XX-X	14"-16"	COTTONWOOD	2	614.0343
XXX.XX W.B. RT.	XX-X	36"	COTTONWOOD	3	614.0352
XXX.XX W.B. RT.	XX-X	6" - 12"	EXISTING STUMPS	6	614.0394
XXX.XX W.B. RT.	XX-X	28"	COTTONWOOD	1	614.0353
XXX.XX W.B. RT.	XX-X	17"	COTTONWOOD	3	614.0333
XXX.XX W.B. RT.	XX-X	14"	BOX ELDER	1	614.0333
XXX.XX W.B. RT.	XX-X	14"	ASH	1	614.0333

614.031X	TREE REMOVAL (UP TO 6" DBH)
614.032X	TREE REMOVAL (OVER 6" TO 12" DBH)
614.033X	TREE REMOVAL (OVER 12" TO 18" DBH)
614.034X	TREE REMOVAL (OVER 18" TO 24" DBH)
614.035X	TREE REMOVAL (OVER 2' TO 3' DBH)
614.036X	TREE REMOVAL (OVER 3' TO 4' DBH)
614.037X	TREE REMOVAL (OVER 4' TO 5' DBH)
614.038X	TREE REMOVAL (OVER 5' TO 6' DBH)

DATE	DESCRIPTION	BY	SYM
REVISIONS			
NEW YORK STATE THRUWAY AUTHORITY DEPARTMENT OF ENGINEERING 200 SOUTHERN BLVD., ALBANY, N.Y. 12209			
TITLE OF PROJECT TITLE OF PROJECT LINE 1 TITLE OF PROJECT LINE 2			
LOCATION OF PROJECT LOCATION OF PROJECT LINE 1 LOCATION OF PROJECT LINE 2			
TITLE OF DRAWING TREE REMOVAL			
CONTRACT NUMBER: TA		DATE: 06/09/11	
DRAWING NUMBER: TR-1			